MISCELLANEOUS DEPARTMENTS.

GOVERNMENT OF MYSORE ELECTRICAL DEPARTMENT.

Notice dated 14th July 1925.

1. Notice is hereby given that sealed tenders will be received at the Office of the Chief Operator, Cauvery Power Scheme, Transformer House, Champion Reefs, up to 31st July 1925, for extending the cooling water Reservoir at Kolar Gold Fields Transformer Station. The tenders will be opened in public at 3 P.M. on Friday the 31st July 1925. The work should be completed within three months from the date of acceptance of the tender.

2. The plans, detailed estimates, and conditions may be obtained at the Office of the undersigned, between the hours, 8 A.M. to 4 P.M. on any working day.

3. Tenders should be submitted in the usual form and should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed. The rate should be in figures as well as in words.

4. The final acceptance of the tender will rest with the Chief Electrical Engineer who is not bound to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Each tender must be accompanied with an earnest money of Rs. 100 in cash or Government Promissory Note and be superscribed "Tender for extending the cooling water Reservoir at Kolar Gold Fields," in default of which, tenders will be rejected.

6. Within five days from the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which, his tender will be considered as cancelled and the earnest money will be forfeited.

7. The name of the successful tenderer will be posted in both the offices of the Chief Electrical Engineer to the Government of Mysore, Bangalore, and the Chief Operator, Kolar Gold Fields, Champion Reefs, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. The construction work should be started within a week from the notification of acceptance of tender.

9. On acceptance of any of the tenders, the earnest money on the rejected tenders will be returned.

Statement showing the approximate quantities of works for extending the cooling water Reservoir at Kolar Gold Fields, Champion Reefs.

No.	Items of works	Per	Quantity
1	Dismantling the wall stone in mortar	C.ft.	87
2	Earthwork excavation hard gravel including removing to a distance within a furlong and refilling trenches where necessary.	C.yd.	163
3	Metal concrete in surki mortar	C.ft.	514
4	Stone in surki mortar	,,	1,017
5	Stone slabs 6" thick, exposed parts dressed	Sq.ft.	58
6	Bond stones fixed in chunam 1½' x 1½' x ½'	Each	26
7	Wire cut brick in cement	C.ft.	219
8	Burnt brick in mortar	,,	59
9	Cement plastering ½" thick	Sqr.	7·93
10	Chunam plastering	,,	2·36
11	Cement pointing	,,	10·10
12	Stone in mortar coping pointed with cement 6" deep	R.ft.	43
13	Second hand M. G. Rails fixed complete with hook, bolts including drilling holes.	Each	28
14	Steel I Beams fixed complete with painting	Cwt.	21
15	4" diameter galvanized iron pipes fixed complete	R.ft.	60
16	Roofing with cudappah slabs 1½" thick with 3" con. and 2 courses of flat tiles with chunam plaster ½" thick on top and bottom surface cement pointed.	Sq.ft.	7·98
17	Rain water down pipes 3" dia. 3' long made of galvd. iron sheet	Each	4
18	4" outlet pipe fixed complete	R.ft.	50

LOUIS J. GORDON,
Chief Operator.

GOVERNMENT SOAP FACTORY, BANGALORE.

Notice dated 13th July 1925.

It is hereby notified for the information of the public that the following articles will be sold by auction, either by batches or single as is found convenient at the time of auction, on Saturday the 1st August 1925, between 3 and 5 P.M., at Government Soap Factory, Bangalore. The articles will be sold to the highest bidder who will have to take delivery of same on